



John R. Kasich, Governor
Mary Taylor, Lt. Governor
Ohio E.P.A.
Craig W. Butler, Director

JUN 25 2015

JUN 25 2015

ENTERED DIRECTOR'S JOURNAL

Nathan Taylor, Environmental Manager
Republic Waste Services
5131 Drinkle Road
Amanda, OH 43102

Re: Pine Grove Regional Facility
Director's Authorization
Approval
Municipal Solid Waste Landfills
Fairfield County
MSWL018818

**Subject: Pine Grove Regional Facility, Fairfield County
Alternative Daily Cover Material Approval
Auto Shredder Residue**

Dear Mr. Taylor:

On May 22, 2015, the Ohio Environmental Protection Agency (Ohio EPA), Division of Materials and Waste Management (DMWM), Central District Office (CDO) received a request from Pine Grove Regional Facility (Facility) located in Fairfield County to continue to apply auto shredder residue (ASR) as an alternative daily cover (ADC) material for an additional ninety (90) days at the Facility. Ohio EPA initially approved a 180-day temporary authorization for the use of ASR as ADC on December 29, 2014, which will expire on June 27, 2015. Republic Waste Services (RWS) is the owner and operator of the Facility.

OAC Rule 3745-27-19(F)(3)(a) states, "The director may approve solid waste to be used as alternative material for daily cover if the owner or operator can demonstrate to the satisfaction of the director that the solid waste material proposed for use can provide protection comparable to six inches of soil and is protective of human health and environment. The owner or operator must obtain written approval to use solid waste for alternative daily cover prior to utilizing the solid waste."

Ohio EPA has reviewed the information contained in the request and has determined that ASR has the potential to provide protection comparable to six (6) inches of soil as required by OAC Rule 3745-27-19(F). Therefore, pursuant to OAC Rule 3745-27-19(F)(3)(a), I hereby authorize RWS to continue use ASR as ADC material at the Facility for a trial period of ninety (90) days from the effective date of this authorization.

As part of this approval, RWS is subject to the following conditions:

CONDITIONS

1. This approval is limited to the use of only ASR at the Facility. No other ADC material may be used at the Facility without prior authorization from Ohio EPA.
2. RWS shall place ASR over exposed waste materials by the end of each working day, or more frequently if necessary, to control fire hazards, blowing litter, odors, dust, insects, birds, rodents, or other vectors. ASR shall be applied such that all waste materials are completely covered. Prior to placing the next layer of waste, ASR shall be removed or otherwise prepared as necessary so as not to impede the flow of leachate to the leachate management system. Any ASR removed prior to placing the next layer of waste shall be disposed of and not re-used as ADC.
3. If inclement weather conditions render the placement or use of ASR ineffective or otherwise unsatisfactory, RWS shall temporarily revert to using conventional soil cover in accordance with OAC Rule 3745-27-19(F) until such conditions cease to exist. Under such circumstances, RWS may apply another ADC material that has been approved for use at the Facility, provided that the ADC material is able to perform effectively under the inclement conditions.
4. If RWS determines ASR is ineffective or otherwise unsatisfactory under normal operating conditions, RWS shall immediately revert to using conventional soil cover in accordance with OAC Rule 3745-27-19(F). Under such circumstances, RWS may apply another ADC material that has been approved for use at the Facility. RWS shall verbally notify Ohio EPA, DMWM, CDO and Fairfield Department of Health of this action by the end of the next working day and shall submit written notification to Ohio EPA, DMWM, CDO within fourteen (14) calendar days. This notification is not necessary if use of ASR ceases only on a temporary basis in accordance with Condition Number 3.
5. If Ohio EPA or Fairfield Department of Health determines that the use of ASR is ineffective or otherwise unsatisfactory under normal operating conditions, then permission to use ASR may be revoked upon written notification from the Director of Ohio EPA (Director). Immediately upon such revocation, RWS shall cease using ASR as ADC material at the Facility and shall revert to using conventional soil cover in accordance with OAC Rule 3745-27-19(F). Under such circumstances, RWS may apply another ADC material that has been approved for use at the Facility.
6. ASR shall not be used as intermediate cover or final cover at the Facility. Any solid waste disposal area that has been covered with ASR and inactive for a period of one (1) day following placement of ASR shall be covered with at least

six (6) inches of soil, in accordance with OAC Rule 3745-27-19(F), not later than the end of the next calendar day following the day the ASR was placed.

7. The use and location of ASR shall be documented in the required Municipal Solid Waste Landfill Daily Log of Operations, Form 3 on each day it is used as ADC material.
8. Not later than forty-five (45) days after the effective date of this authorization, RWS shall submit a report to Ohio EPA, CDO comparing the effectiveness of using ASR to conventional soil cover. The report shall contain a discussion of the following items:
 - a. The number of days that ASR was used;
 - b. Weather conditions at the time of placement of ASR;
 - c. Number of days odors were detected;
 - d. The presence of vectors, rodents, or insects;
 - e. Any increase in blowing litter;
 - f. Any incidents of fire at the working face during use of ASR as ADC;
 - g. Methods for controlling fire during use of ASR;
 - h. Any increase or decrease in the amount of erosion as compared to areas with conventional soil cover.
9. This authorization to use ASR as ADC material shall expire ninety (90) days after its effective date. RWS shall not continue to use ASR after this date unless the report required by Condition 8 is submitted and authorization for the continued use of ASR as ADC material is granted.
10. Photographs from at least two opposing sides of the working face shall be taken each day that ASR has been applied. All photographs shall be maintained at the Facility and made available to Ohio EPA and Fairfield Department of Health upon request. The photographs shall be marked with the date and time that the photograph was taken along with the name of the photographer, the direction the picture was taken, and a description of the general area in which the photograph was taken.

11. ASR shall only be applied as ADC material on interior slopes of the landfill where surface water that may contact the ASR will be contained within the confines of the leachate collection system.
12. ASR shall be placed as ADC material in the wet form that comes directly from Columbus Auto Shredder Inc. and placed as ADC material on the same day as delivery. Any ASR delivered to the Facility which is not used for ADC shall be disposed at the Facility on the same calendar day it is delivered to the Facility.
13. All appropriate state and local solid waste fees shall be applied to the ASR, regardless of whether it is temporarily stored, utilized as ADC material, or disposed of in the working face.
14. Any ASR brought to the Facility for disposal or use as ADC material shall be counted toward the Facility's authorized maximum daily waste receipt.
15. All stockpiles or storage areas for the ASR shall be located within the current phase of operation. Any water that comes into contact with the ASR, either during use as ADC material or during storage, shall be directed to the leachate collection system.
16. Nothing in this letter shall be construed to authorize any waiver from the requirements of any other applicable federal or state laws or regulations. This letter shall not be interpreted to release RWS from responsibility under ORC Chapters 3704, 3714, 3734 or 6111; under the Federal Clean Water Act, the Resource Conservation and Recovery Act, or the Comprehensive Environmental Response, Compensation, and Liability Act; or from other applicable requirements for remedying conditions resulting from any release of contaminants to the environment.


You are hereby notified that this action of the Director is final and may be appealed to the Environmental Review Appeals Commission pursuant to Ohio Revised Code Section 3745.04. The appeal must be in writing and set forth the action complained of and the grounds upon which the appeal is based. The appeal must be filed with the Commission within thirty (30) days after notice of the Director's action. The appeal must be accompanied by a filing fee of \$70.00, made payable to "Treasurer, State of Ohio." The Commission, in its discretion, may reduce the fee if by affidavit it is demonstrated that payment of the full amount of the fee would cause extreme hardship. Notice of the filing of the appeal shall be filed with the Director within three (3) days of filing with the Commission. Ohio EPA requests that a copy of the appeal be served upon the Ohio Attorney General's Office, Environmental Enforcement Section. An appeal may be filed with the Environmental Review Appeals Commission at the following address:

Nathan Taylor
Republic Waste Services
Page 5

Environmental Review Appeals Commission
77 South High Street, 17th Floor
Columbus, OH 43215

If you have any questions regarding this authorization, please contact Allan Hurtt of Ohio EPA, DMWM, CDO at (614) 728-3889.

Sincerely,

A handwritten signature in black ink that reads "Craig W. Butler". The signature is written in a cursive style with a large initial "C" and a prominent "W".

Craig W. Butler
Director

c: Melissa Storch, DMWM, CDO
Scott Hester, DMWM, CO
Jennifer Valentine, Fairfield Department of Health
Ron Zitek, North Point Engineering

AH/cf PineGroveTemporary ADC extention