

RE: Country Acres Golf Club
Report
Drinking Water Program
Putnam County
PWS ID: OH6901412

Country Acres Golf Club

17374 St. Rt. 694
Ottawa, OH 45875
(419) 532-3728 Fax (419) 532-3432
e-mail: jhcgcs@bright.net
OH6901412: Facility ID: 6957589

RECEIVED

FEB 15 2017

OHIO E.P.A.
N.W.D.O.


Lead & Copper Water System Narrative:

Country Acres Golf Club was built in the summer of 1977. In October of that year I came in as the Golf Course Superintendent. The following fall (1978) the lines were installed for our potable water system. I oversaw the construction and can verify that all of the water lines consist of PVC pipe, varying from 8", 6", 4", 3" and 2" piping. The service connections to all of the houses and buildings consist of Dresser Style 0294 quick taps, (or equivalent) with 1" pvc, or poly piping for supply lines.

The only buildings in the development that have copper plumbing would be the Clubhouse for the Golf Course and the Huey Investment Apartments. The Clubhouse was built in 1980 and the Apartments in the later 80's or early 90's. They are both highlighted on the map.

All single family dwellings and other buildings are plumbed with PVC or CPVC piping.

Respectfully Submitted:



James R. Hemrick CGCS



COUNTY ROAD J

ISOLATION VALVE



NOTE:
 FORCED SEWER
 MAIN - WILL
 MAINTAIN 18"
 VERTICAL SEPARATION
 (NO OTHER UTILITY
 CROSSES.)

PROPOSED
 ADDITION

STATE ROUTE No. 694

ALL SERVICE CONNECTIONS TO BE
 MADE WITH DRESSER STYLE
 0294 QUICKTAP SVC. CONN.
 ALL LINES 4' DEEP
 MIN. 10' HORIZONTAL SEPARATION
 MAIN - SEWER
 MIN. 18" VERTICAL SEPARATION
 MAIN - SEWER CROSS OVERS
 ALL LINES TO BE PVC - SDR 26
 NSF PW ASTM D-224
 PRESSURE MAINTAIN 50 PSI

WATER SUPPLY
 APPROVED
 OHIO ENVIRONMENTAL PROTECTION AGENCY
 AS EVIDENCED BY COPY OF
 LETTER OF APPROVAL
 HERETO ATTACHED

ISOLATION VALVES

LINE TO BE 10' FROM R

SCALE - 1" = 200'

LC 207

LC 209

LC 205

LC 208

LC 210

LC 204

LC 206

STATE ROUTE No. 694

RECEIVED
 FEB 15 2017
 OHIO E.P.A.
 N.W.D.O.

NO-4981WS
 Amount \$ 110.00 Date 2/14/17
 Check # 2282 Date 2/14/17

RECEIVED
 MAY 14 2002
 OHIO E.P.A.
 N.W.D.O.