

RE: Swancreek Water District 1
Report
Drinking Water Program
Fulton County
PWS ID: OH2601412


**VERIFICATION FORM FOR COMMUNITY PUBLIC WATER SYSTEMS
CLAIMING NO LEAD SERVICE LINES**

The owner or operator of all community public water systems must identify and map areas of their distribution system that are known or are likely to contain lead service lines. Systems must submit a copy of the applicable map to the Ohio Department of Health and the Ohio Department of Job and Family Services. Systems must also submit a report to the director containing at least both of the following: (1) The applicable map with narrative, and (2) A list of sampling locations used to collect samples as required by Ohio Revised Code (ORC) Section 6109.121 and any rules adopted thereunder, including contact information for the owner and occupant of each sampling site.

Should a water system determine no lead service lines exist in their distribution system, they must provide information stating they reviewed, at the minimum, historical permit records and local ordinances, distribution maintenance records and information pertaining to installation dates or materials for all services lines. This information must be verified below.

I HEREBY CERTIFY THAT THE FOLLOWING METHOD(S) WERE USED TO DETERMINE NO LEAD SERVICE LINES EXIST IN THIS WATER SYSTEM'S DISTRIBUTION SYSTEM, AS REQUIRED BY ORC 6109.121(F):

LEAD SERVICE LINE VERIFICATION
<p>This PWS states they have no lead service lines and has reviewed the following information (select one or more of the following):</p> <ul style="list-style-type: none"><input checked="" type="checkbox"/> Historical permit records and/or local ordinances<input type="checkbox"/> Distribution maintenance records (i.e. meter replacement, waterline break repairs)<input checked="" type="checkbox"/> Information pertaining to installation dates for all service lines (i.e. after 1986 when lead services lines were banned)<input checked="" type="checkbox"/> Service line material of all service lines is known (i.e. all service lines are known to be PVC)



Signature of Responsible Person

3-7-2017

Date

Ziad Musallam, Operator-of-Record

Printed Name and Title of Responsible Person

PWS NAME: Swancreek Water District 1

PWS ID: OH2601412

COUNTY: Fulton

For Ohio EPA use only:

Date Verification Rec'd: _____

Lead Mapping Verification Form Revised 2/14/17

RECEIVED

MAR 08 2017

DDAGW - NWDO

LEAD SERVICE LINE CERTIFICATION

WATER SYSTEM Swan creek Water District 1

OWNER Swan creek Water District

PWS ID OH2601412

SERVICE AREA Western Swan creek TWP

This lead service line certificate applies to all current premises that are served by the above listed water system. Based on the following documents, this water system has no records of lead service lines within the current service area:

1. Swan creek Water District Fulton County Service Line Specifications – Copper or PVC service line materials – Specifications Included.
2. The entire water system was substantially completed and placed in operation in 2001.

Ziad Musallam, PE
Operator-of-Record

Signature:  Date: 3-7-2017

RECEIVED
MAR 08 2017
DDAGW - NWDO

Swan Creek Water District

5565 County Road D
Delta, OH 43515

Phone: 419-822-3656

Email: swan creekwater@windstream.net

FAX: 419-822-3656

TO: Residents **with a Curb Stop** interested in Hooking up to the City Water
FROM: Swan Creek Water District
DATE: January 2, 2015 (Last Revisions)
RE: Information Packet on Getting Hooked Up to the Water Main System

Property owners who are not licensed contractors may install their own service lines, but may only dig up to 10' from the curb stop. However, only contractors who are registered with the Water District are permitted to expose or make the actual connection from the service line to the District's Water System. This includes the installation of the meter.

You may not connect any two systems together in any manner that could cause contamination to the District's water supply. For example, you may not connect your well water to the Water District's water supply. No cross connections are allowed.

Registered Contractors

See attached list of contractors who are registered with Swan Creek Water District. These contractors are insured and bonded and are authorized to do all the work required to install and connect your water service.

Material Specs for Water Line from the Road to the House

- 1" K-Copper or SDR9, 200 PSI Plastic with Tracer Wire; at least 14 gauge May be used.
- Depth of Line - 4 Feet Minimum

Connection Fees & Meters

- The meters must be purchased by the homeowner from the Swan Creek Water District and the cost is \$275.00. This cost **only** includes the meter, pressure-reducing valve and a remote reader which will be installed by our inspector.
- The meters will be placed inside the homes and must be in a heated location that is easily accessible to Swan Creek Water District personnel for purposes of inspecting and maintaining the water meter. Any other location needs contractor recommendation and inspector authorization prior to installation. If the homeowner wishes to incur additional costs for a meter pit (an outside meter which is installed in a pit where the service line connects to the District's main water line), please see "meter-pit" notes.
- The water meters are the property of the District and may be changed, maintained and altered solely at the District's discretion. Upon notification by a customer of a suspected faulty or inaccurate meter the District shall replace the meter. If the replaced meter is found to be accurate within the manufacturer's limits, the District may levy a replacement charge. A suspected inaccuracy or faulty meter is not grounds for non-payment of a bill.

RECEIVED

MAR 08 2017

DDAGW - NWDO

Meter Pits

- Meter pit is required if the dwelling is more than 250 feet off the road and/or if there is a ditch crossing between the curb stop and dwelling.
- Meter Pit Specs - 30" plastic meter pit for a 1" meter and it must have a metallic lid with a hole for the remote reader's transmitter. This pit must be installed by a registered contractor and must be adjacent to the curb stop.

Inspections

- An inspection must be done by the Swancreek Water District prior to turning on the service. The cost for an inspection is **\$50.00** based on a 1-hour inspection. If there are problems with the line or the connections and more time is required, the rate is \$50.00 per hour.
- The Swancreek Water District shall be given at least 48-hours notice when an inspection is required. In order to minimize the interruption of water service, the contractor is responsible to schedule the inspection.
- A Swancreek Water District Inspector must be present when tap is made at the curb stop.
- Note: The entire trench needs to be left open for inspection.
- The inspector will be doing the following:
 1. Checking the Connection at the curb Stop
 2. Checking the Service Line for Depth, Material Used, and Making Sure there are no Cross Connections
 3. Check the Meter Assembly and Installing RTR
 4. Turning Service On and Checking For Leaks

Water Rates & Billing

- **Current Minimum Monthly Charge:** Every residential customer, regardless of the amount of water actually used, shall pay a minimum charge of \$26.58 per month per. If you exceed the minimum amount, you will just be charged the standard water rate.
- The minimum monthly charge is based on 2,500 gallons or less usage and shall be charged regardless of whether or not the water service is used during the month, including seasonal disconnections.
- **Standard Water Rate:** The current monthly service charge shall be based on the number of gallons of water consumed as follows: \$10.63 Per 1,000 Gallons.
- **Billing** is done every two months. (February, April, June, August, October and December) The minimum bi-monthly charge will be \$53.15 and this is based on 5,000 gallons or less usage.

Application for Residential Tap Permit

- A permit is required. We have enclosed an Application for Residential Tap Permit. You may not have any connections made prior to obtaining a tap permit. In order to obtain a tap permit, the District will need this completed application along with payment for the meter, remote reader, regulator, and inspection (**\$325.00**). Please make checks payable to Swancreek Water District.

In compiling this information, we have tried to answer all questions that may arise. However, if you have any other questions or concerns, please feel free to call our office at (419) 822-3656.

Board Members:	Mark Fowler, Dale Brunner, Randy Walker, Shawn Albert, Walt Lange
Manager:	Tina Whalen
Assistant:	Cindy Fowler
Inspector:	Tom Shelley

RECEIVED
MAR 08 2017
DDAGW - NWDO


Lead Service Map

Status

- Public Not-Lead, Private Not-Lead
- Public Not-Lead, Private Unknown

Legend

- Parcels
- Building Outlines
- Roads



Lead Service Map
Swan Creek Water District # 1 – PWS ID OH2601412

Created by FC GIS, S Yoder Date: 3/8/2017

*Buildings in Ohio built prior to 1998 or that use plumbing material or solder manufactured before 1998 may have materials with greater than 8% lead and are at a higher risk of contributing lead to the drinking water than materials manufactured after 1998. In addition, buildings built and plumbing materials manufactured after 2014 were required to have less than 0.25% lead by weight and have the lowest risk for contributing lead to the drinking water. It should be noted however that, although prohibited, some use of leaded solder or leaded components may have occurred after the prohibition became effective.